



Arizona Pool Covers LLC

943 South 48th St. Suite #118 Tempe, AZ 85281
Central Arizona Phone (480) 829-0083 Fax (480) 829-1101
Southern Arizona Phone (520) 408-1579
schedule@azpoolcovers.com

Time of events with automatic cover construction

- 1) Designer creates pool with cover and receives or creates cover estimate.
- 2) Pool is sold. Designer drawings go to construction for processing
- 3) ***Recommend sending drawing of pool to Arizona Pool Covers at this time. Therefore, Arizona Pool Covers can review the cover details and try and prevent possible errors before the pool is constructed. And be aware of possible special scheduling needs for the builder. Sales agreement is signed with Arizona Pool Covers, deposits required. Color selections for fabric and powder coating are required for order processing.***
- 4) Excavation including area for cover housing.

CALL OR EMAIL OUR OFFICE TO ADVISE OF EXCAVATION SCHEDULE EVENT

- 5) Electric. control switch and cover housing ***may require wiring diagrams*** for type of control purchased
- 6) Plumbing Drainage from cover housing. At end of cover housing
- 7) Steel including area for lower beam and cover housing

CALL OR EMAIL OUR OFFICE AT PRE GUNITE

- 8) Gunitite ***Cover may be measured and ordered at this time if requested. This will reduce the delivery delay at the end of the pool construction phase. Pools using "Vanishing Trays" see cover housing on sales agreement require special order vanishing trays (ordered after gunitite with at least 2 week processing time) to be at jobsite. Required at deck.***

CALL OR EMAIL OUR OFFICE AS SOON AS DECK IS SCHEDULED

- 9) Tile Tile lower beam, Front and rear have ¼ round or Bullnose
- 10) ***Track installation before deck is installed. Travertine, vertical walls may require special scheduling and materials. We request a week notice to schedule effectively. This is the standard time of measurements and ordering the pool cover system.. Typical material & order processing time 2-3 weeks. Powder coating or special orders may create delays. Track may be placed into preinstalled pool builder forms when requested.***
Contract and deposit required, before tracks delivered at this phase

- 11) Decking If pool has vanishing trays, trays to be at jobsite prior to decking.
 Pools with vanishing trays may require additional deposit at tray delivery.
- 12) Wires pulled

CALL OR EMAIL OUR OFFICE THE DAY POOL INTERIOR IS SCHEDULED

- 13) Cover can be installed at this point. Some inspectors request the unit (no fabric) installed before final inspection is approved.
PLEASE ADVISE OUR OFFICE 520-408-1579 OR 408-829-0083 OF ANTICIPATED INSTALLATION DATE AS SOON AS POSSIBLE
Final payment required prior to installation. FINAL INSTALLATION IS AFTER WATER IN POOL

Standard processing time is 2 – 3 weeks from time of measurements. Please keep our office informed of schedule change