

## Time of events with automatic cover construction

- 1) Designer creates pool with cover and receives pool cover estimate.
- 2) Pool is sold. Designer drawings go to construction for processing
- 3) ***Recommend sending drawing of pool to Arizona Pool Covers at this time. Therefore, Arizona Pool Covers can review the cover details and try and prevent possible errors before the pool is constructed. And be aware of possible special scheduling needs for the builder. Sales agreement is signed with Arizona Pool Covers, deposits required. Color selections for fabric and powder coating are required for order processing.***
- 4) Layout / Excavation. Including area for cover housing. Possibly a dry well for drainage at time of pool excavation.

### CALL OR EMAIL OUR OFFICE TO INFORM OF EXCAVATION & GUNITE SCHEDULE EVENT

- 5) Electric. Control switch and cover housing ***may require wiring diagrams*** for type of control purchased. Contact Arizona Pool Covers for correct diagram.
- 6) Plumbing Drainage from cover housing. At end of cover housing
- 7) Steel Including area for lower beam and cover housing. Lowered internal spa walls
- 8) Gunite ***Cover may be measured and ordered at time if requested.***  
***This will reduce the delivery delay at the end of the pool construction phase.***  
***Pools using "Vanishing Trays" (see cover housing on sales agreement) require special order vanishing trays (ordered after gunite with at least 2 week processing time) to be at jobsite.***  
***Vanishing lid systems may present special and unique elevation requirements***
- 9) Tile Water line tile and lowered beam, front and rear of lower beam should have 1/4 round or bull nose. Interior spa wall edges should have rounded edges on tile.

### **Contract, signatures and deposit required with Arizona Pool Covers before track can be scheduled or delivered.**

- 10) ***Track installation before coping is installed. Vertical Walls may require special scheduling and materials.***  
***Track channel applications: prepare top of beam to be flat and level at least 6 in. away from waters edge.***  
***Stainless steel strap applications: Prepare top of beam to be flat and level at least 10 in. away from waters edge.***

### **We request a week notice to schedule effectively.**

***This is the standard time of measurements and ordering the pool cover system.***

***Typical material & order processing time 2-3 weeks. Powder coating or special orders may create delays.***

***Track may be placed into preinstalled pool builder forming when requested.***

- 11) Coping/Decking If pool has vanishing trays, trays to be at jobsite prior to decking. (poured deck application only)
- 12) Wires pulled

### CALL OR EMAIL OUR OFFICE THE DAY POOL INTERIOR IS SCHEDULED

- 13) Cover can be installed at this point. Some inspectors request the unit (no fabric) installed before final inspection is approved.  
**PLEASE ADVISE OUR OFFICE 520-408-1579 OR 408-829-0083 OF ANTICIPATED INSTALLATION DATE AS SOON AS POSSIBLE**  
**Final payment required prior to installation. FINAL INSTALLATION IS AFTER WATER IN POOL**

*Standard processing time is 2 – 3 weeks from time of measurements. Please keep our office informed of schedule change*